

Nabagram Amar Chand Kundu College

(Govt. aided & affiliated to the University of Kalyani)

Nabagram * Murshidabad * Pin – 742184

Website: www.nabagramackcollege.in or www.nackconline.com

* Phone: 9907464847 * Email: nackcollege@yahoo.com



28/09/2023

TENDER TOTICE

Sealed Quotations are invited from reputed vendors within seven days from the date of publishing the notice for the following renovation works/purchase of equipment etc. For each of the following jobs separate quotations are required. Quotations put together for multiple jobs are liable to be cancelled. For any further clarification you may contact college office. The decision of the college purchase committee will be final.

JOB No. 1: Partition work to set up a waiting room

Job Details: (i) Setting up Al Channel (1.3 mm) with ACP and frosted/etched glass partition (Total Area = 261 sq ft)

ii) Setting up Al Channel (1.3 mm) with ACP and frosted/etched glass sliding window (Total Area = 166 sq ft)

JOB No. 2: Remodeling of Administrative Office

Job Details: Setting up Al Channel (1.3 mm) with ACP and frosted/etched glass partition (Total Area = 422 sq ft)

JOB No. 3: Construction of Departmental Staff-room cubicles

Job Details: Setting up Al Channel (1.3 mm) with ACP and frosted/etched glass partition (Total Area = 408 sq ft)

JOB No. 4: Construction of Ladies Common Room

Job Details: Setting up Al Channel (1.3 mm) with ACP and frosted/etched glass partition (Total Area = 416 sq ft)

JOB No. 5: Computer room set-up

Job Details: Purchase and installation of 3 dual-inverter split 1.5 ton AC

JOB No. 6: Wooden table top for staff-room cubicles

Job Details: Construction of 6 (six) L-shaped (Compressed wood/plywood) table top with polished finishing. Length of each arm 10 ft. Breadth of the table 2.5 ft and height 2.5 ft.

JOB No. 7: Restructuring Principal's office

Job Details: (i) Construction of False ceiling with (Gypsum board). Total area: 600 sq ft

(ii) Repainting the walls (Scraping old paint followed by stepwise application of , Polymer Putty , Primer and Premium Interior Emulsion).

(iii) Painting and false ceiling job in two attached washrooms.

JOB No. 8: Office furniture

Job Details: (i) Construction curved L-shaped (One arm 8 ft and the other one 4 ft long. Width of the long arm 3ft and short arm 2.5 ft respectively. Height 2.5 ft, Four drawers) executive table with Teak (Segun) wood. Table top will be covered with designer glass.

(ii) One designer display cabinet (Length 8 ft, width 1.5 ft and height 7ft) made up of water-proof ply in polished finishing.

(iii) Wall mounted designer semi-arched display board (6 ft wide and 10 ft high).

(iv) One sofa set

JOB No. 9: Installation of CCTV

Job Details: Installation of CCTV with following items

- (i) 32 inch LED TV
- (ii) 32 port DVR
- (iii) 14 good quality CC camera

JOB No. 10: Construction of washroom for Divyang students

Job Details: (i) Setting up a toilet with commode, corner wash-basin, and laying tiles on wall and floor.

(ii) Laying tiles (2 ft by 4 ft size) on 620 sq ft floor area

(iii) Laying wall tiles (1 ft X 2ft) and floor tiles (16 inch X 16 inch) in 2 wash rooms.

JOB No. 11: Setting up iron gate and iron fencing

- Job Details:** (i) Construction and installation of iron gate (17 ft X 7 ft) beside the school entrance.
(ii) Construction and setting up iron fencing alongside the play-ground (400 sq ft) side gate
(iii) Construction and setting up high (6ft) iron fencing with net in the west side of the herbal garden.
(iv) Repairing the damaged fencing

JOB No. 12: Setting up iron gate for pedestrians with cattle trap

- Job Details:** (i) Construction and installation of iron gate with cattle trap beside the college main entrance
(ii) Construction and installation of 3 Grill-made gates
(iii) Construction and installation of 2 iron-sheet doors with frame and shutter lock

JOB No. 13: Repairing Girl's washroom

- Job Details:** (i) laying tiles on the wall (700 sq ft) and floors (320 sq ft).
(ii) 5 (five) Al Channel—doors.
(iii) Relaying 5 (five) toilets with 4 (four) in Bengali style and one commode

JOB No. 14: Modification of existing electrical wiring

Job Details: Electrical lines/ switches etc need to be relayed to fulfil the requirements of the remodeled portion of the college premises. [For further details visit college].

JOB No. 15: Purchase and installation of electrical equipment/tools

- Job Details:** (i) Purchase and installation 20 BLDC ceiling fans
(ii) Purchase and installation Tube lights (30)
(iii) Purchase and installation False ceiling lights

JOB No. 16: Replacements of flush-doors

- Job Details:** (i) Purchase and installation of 5 (five) tata flush doors with frame
(ii) Purchase and installation of 8 (Eight) designer PVC flush doors for bath rooms
(iii) Purchase and installation of 5 (five) Al -channel doors

JOB No. 17: Construction of Alumni Association Office

Job Details: (i) Setting up Al Channel (1.3 mm) with ACP and frosted/etched glass partition (Total Area = 104 sq ft)

ii) Setting up Al Channel (1.3 mm) with ACP and frosted/etched glass sliding window (Total Area = 90 sq ft)

(iii) Purchase and installation of 1 dual-inverter split 1.5 ton AC

(iv) Purchase of 1 sofa set

JOB No. 18: Purchase and installation of Computer

Job Details: Purchase and installation of 9 Computers with the following specifications:

Intel i3 3rd Gen CPU

61 Motherboard

8 GB Ram DDR3

128 GB SSD

SMPS 450W

Cabinet

Keyboard and mouse Combo

19" Monitor (HDMI)



Principal
Nabagram Amar Chand Kundu College
Nabagram, Murshidabad

